

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of Work: Detailed Estimate for the Work of Drilling of Borewells, and Other Developmental Works for Providing Drinking Water Facility in thanisandra Rachenahalli, Dasarahalli Mariyannapalya and Maestripalya and other Surrounding area in ward no. 06.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	11	Geophysical investigation of site for sinking borewell for supplying drinking water to the habitation either through the hand pump, MWS or P.W.S.S. by vertical electrical sounding by adopting venner or schlumbergers's method, including reconnaissance survey of geological formation, Geological investigation of existing ground water in vicinity, its quality, quantity & acceptability of the users indicating the location of site, recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 mtr in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site, engaging technical personal and labour required etc (P.NO-47, I.NO-9.4, PRED 12-13 SR)	Each BW	1938.48 <i>1938.46</i>	Rupees One Thousand Nine Hundred Thirty Eight and Forty Eight Paise Only <i>Six</i>
2	550	Sinking of borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for one hour(excluding cost of casing pipes, collars, cap etc.,) (P.NO-47, I.NO-9.1, PRED 12-13 SR) 0 to 50 m	Rmtr	315.18	Rupees Three Hundred Fifteen and Eighteen Paise Only
3	550	50 to 100 m		412	Rupees Four Hundred Twelve Only
4	550	100 to 150 m		458.35	Rupees Four Hundred Fifty Eight and Thirty Five Paise Only
5	550	150 to 200 m		484.10	Rupees Four Hundred Eighty Four and Ten Paise Only
6	550	200 to 250 m		560.32	Rupees Five Hundred Sixty and Thirty Two Paise Only
7	660	250 to 310 m		600.49	Rupees Six Hundred and Forty Nine Paise Only
8	495.00	Supplying of ISI Mark 175 mm nominal bore medium black ERW casing pipe of 5mm thick black electric resistance continous welded midle steel tube material confirming to IS 1387/1993 and manufactured from hot rolled steel skelp/stripes in random length of 4 to 7 mtr both ends threaded confirming to IS 554/1985 one end(including of all taxes) (P.NO-III, I.NO-84, PRED 12-13 SR)	Rmtr	1364.75	Rupees One Thousand Three Hundred Sixty Four and Seventy Five Paise Only
9	143.00	Providing and fixing 250mm dia PVC pipe and as per specification and directions. (BWSSB SR 13-14, P.No.53 I.no.1 of sl.no.11.)	Rmtr	1133.00	Rupees One Thousand One Hundred Thirty Three Only
10	11	175 mm dia M.S. Casing cap (P.NO-III, I.NO-85, PRED 12-13 SR)	Each	103.00	Rupees One Hundred Three Only

No of corrections - Three (03)

E.E. (B.T. CIV)
11/10

Quantity.	Description	Unit	Rates	
			In Figures	In Words
88	M.S. Casing pipe collars 'C' Class (P.NO-III, I.NO-86, PRED 12-13 SR)	Each	154.50	Rupees One Hundred Fifty Four and Fifty Paise Only
12	11 Supply & delivery at site brand new texmo/innoval/lubi/sabar /Atalanta/calamal/ waterman/Radha make suitable HP deep well submercible pumpset suitable for vertical installation in 150 dia borewells compressing of single stage or multistage CF pump close coupled by means of stainless steel coupling to suitable HP squirrel cagesubmercible induction motor suitable for operation of 3Ph, 50Hz.380/440 volts AC supply fitted with required accessories such as suction, casing, suction strainers, sand guard. Non return valve etc Complete the pump and motor shall from an integral unit with all the required fittings 15.000 HP 25 stage (P.NO-XXXXIII, I.NO-33, PWD SR 13-14)	No	75541.17	Rupees Seventy Five Thousand Five Hundred Forty One and Seventeen Paise Only
13	2860.00 Providing, laying & jointing GI pipes conforming to IS specification of approved make with fittings such as collars bends elbows tees nipples plugs with cuts threads using white lead & threads for joints wherever necessary as per direction including all lead & lift etc., complete 'A' grade(excluding cost of fittings)b50mm dia GI pipe (SR 13-14 PWD, P.No.XVII SI.no. 509)	Rmtr	340.26	Rupees Three Hundred Forty and Twenty Six Paise Only
14	506.00 Providing & fixing heavy duty collar (P.NO-III, I.NO-86, PRED 12-13 SR)		159.00	Rupees One Hundred Fifty Nine Only
15	5500.00 Supplying and drawing 3 core PVC Sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor conforming to table 3 class 5 of IS: 8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto 1100 volts 4 sqmm of 56 strands 0.3mm dia (P.NO-535, I.NO-30 (c), BWSSB 12-13 SR)	Mtr	164.29	Rupees One Hundred Sixty Four and Twenty Nine Paise Only
16	11.00 Supplying & delivery at site brand new / Essen / Lotus sunsines/Adarsh/ Gk controls best indigenous make combine energy meter-cum-control panel board unit of size 1200 x 600 x 300 mm minimum mechanically strong and vermin and water proof the unit shall have two detachable doors suitable for operation on 3ph, 50Hz, 380/440 volts, AC supply with spring loaded latch locking with a key ribs should be provided inside the door , canopy apron and louvers ventilators shall be provided the combine energy mtr cum control panel board unit suitable for operation on 3ph, 50Hz, 380/440 AC supply shall be consisted etc., completed T panel board shall be fabricated on single unit in the above components panel board for suitable pumpset above components panel board for suitable pumpset above 6.50 HP to 15.00 HP with star delta starter (MR)	No.	14800.00	Rupees Fourteen Thousand Eight Hundred Only
17	242000.00 Fabricating supplying and mounting MS box of 16 SWG suitable for floor / wall mounting, fully weather proof with provision for better hear description, (providing with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primes paint and finally finished with approved colour enamelled metal paint etc., complete box of 21600 sq cm (P.NO-530, I.NO-39 b, BWSSB SR 13-14)	Sqm	0.34	and Thirty Four Paise Only
18	11.00 Providing & Fixing of clamps set and borewell cap to the pump (MR)	No's	690.00	Rupees Six Hundred Ninety Only
19	33.00 Supplying & delivery of brand new best make non return valve of size 50mm as per IS: 778/84 with latest amendments with ISI mark (50mm Gate wheel Valve. (PWD SR 13-14, P.NO.XXIV, SI.no, 673)	No's	1696.00	Rupees One Thousand Six Hundred Ninety Six Only
20	33.00 Supplying and delivery of brand new best make Gate Valve of size 50mm as per IS: 778/84 with latest amendments with ISI mark . 50mm Gate Valve for distributor pipeline. 50mm dia (PWD SR 13-14, P.NO.XXIV, SI.no, 659)	No's	1213.70	Rupees One Thousand Two Hundred Thirteen and Seventy Paise Only
21	33.00 Providing and fixing of 50mm GI bend to motor (PWD SR 13-14, P.NO.XXXVIII GI FITTINGS TABLE)	No's	232.14	Rupees Two Hundred Thirty Two and Fourteen Paise Only

No of corrections - Nil

E.E. (B.T. DIV)
11/01

Quantity.	Description	Unit	Rates	
			In Figures	In Words
33.00	Providing and fixing of 50mm GI Nipple to motor (PWD SR 13-14, P.NO.XXXVIII GI FITTINGS TABLE)	No's	110.56	Rupees One Hundred Ten and Fifty Six Paise Only
23 33.00	Providing and fixing of 50mm GI union to the motor (PWD SR 13-14, P.NO.XXXVIII GI FITTINGS TABLE)	No's	237.12	Rupees Two Hundred Thirty Seven and Twelve Paise Only
24 11.00	Labour Charges for end connection (MR)	No's	400.00	Rupees Four Hundred Only
25 550.00	Labour charges for erection of new /repaired submersible pumpset along with GI pipes (32/50mm) cable (new submersible pumpset if required will be supplied by the department free of cost and released pump set should be handed over to department) including transportation (each length = 6.00m) (P.No - 564, I.No - 3, BWSSB SR 13-14)	Per length	90.64	Rupees Ninety and Sixty Four Paise Only
26 11.00	Erection of combined panel board meter board with all necessary materials and labour including providing CC 1:3:6 foundation bed etc., Complete for basement out door type. (MR)	No's	475.00	Rupees Four Hundred Seventy Five Only
27 11.00	Supplying and fixing miniature circuit breakers/isolators in existing MCB distribution boards using necessary fixing materials and wiring complete as required, 40 to 63 Amps DP (P.NO - 526, I.NO - 13D (a), BWSSB SR 13-14)	No's	906.40	Rupees Nine Hundred Six and Forty Paise Only
28 209.00	Supplying and laying of L.T.U.G Cable having aluminiumconductor PVC insulated shethed galvanised steel wire/ steel tape armoured cable with PVC outer sheathing 1.1 KV class 4 core 16 sqmm cable (confirming to IS 1554) (P.NO - 553, I.NO - 10 (d), BWSSB SR 13-14)	Mtr	169.95	Rupees One Hundred Sixty Nine and Ninety Five Paise Only
29 209.00	Digging of trenches of 0.6mm x 0.50 Mtrs wide refilling the trench to the required ground level and consolidating etc., Complete sutting road surfaces (P.NO - 554, I.NO - 12 (b), BWSSB SR 13-14)	Mtr	56.65	Rupees Fifty Six and Sixty Five Paise Only
30 44.00	Supplying and fixing Class-A GI Pipe on pole/ wall/drain crossing with necessary clamping arrangements for UG Cable of 1.1 KV class 40mm (P.NO - 555, I.NO - 15 (b), BWSSB SR 13-14)	Mtr	294.58	Rupees Two Hundred Ninety Four and Fifty Eight Paise Only
31 11.00	Supplying and fixing wiring earth electrode for grounding conduits, IC cutouts and other equipments on the meter board using 40mm dia 2.90 mm thick GI pipe 2.5 mtr long buried in a pit,/ the pit should be filled with equal proportion of salt and charocal 150 mm around the pipe to complete depth the connections from the pipe to the conduit etc., is to be established though GI wire of size as per ISI specification 7.3.3 of ISI 732 using 12mm dia boalts, nuts washers and checknuts etc., the pipe shall have 16 through holes of 122mm dia (P.NO - 552, I.NO - 7 , BWSSB SR 13-14)	No's	1699.50	Rupees One Thousand Six Hundred Ninety Nine and Fifty Paise Only
32 11.00	Supply and fixing LT cast iron pot heads suitable for 1.1 KV class 16 sqmmUG cable filled with necessary bitumen/ insulating compound complete with terminals, clamps, bolts nuts and washers etc, (P.NO - 555, I.NO - 16 (b) , BWSSB SR 13-14)	No's	271.92	Rupees Two Hundred Seventy One and Ninety Two Paise Only
33 11.00	Supplying shunt capacitor's confirming to IS 2834, 3phase 400/440 volts grade for power factor improvement of roating machinery capacitor in KVAR rating No's. (MR)	No's	1350.00	Rupees One Thousand Three Hundred Fifty Only
34 33.00	Providing and fixing Gun Metal Gate wheel valve confirming to IS specification of approved make as per direction including all lead and lift etc., Complete. 50mm dia (P.NO - 103, I.NO - 13.79.6, PWD SR 13-14)	No's	1515.80	Rupees One Thousand Five Hundred Fifteen and Eighty Paise Only
35 11.00	Supplying and fixing of polished wood board made of not less than 15mm thick plank on both sides with planks made out on not more than 2 pieces and fixing the same to wall using tapered inverted wooden plugs screws etc., Size 20 x 20 x 2.5 inches (P.NO - 521, I.NO - 2 (f), BWSSB SR 13-14)	No's	311.58	Rupees Three Hundred Eleven and Fifty Eight Paise Only
36 45	Labour Charges of lifting of non functioning submersible Pump set along with cable and GI Pipes (BWSSB SR 14-15, P-558 I-1(i))	Each Length	109.00	Rupees One Hundred Nine Only
38 45	Transportation of pumping machineris (P. 56 / I. 10.3.19) PRED SR (2012-13)	Each	900.00	Rupees Nine Hundred Only

No g corrections - nil

11/01
E.E. (BTP. DIV)
11/01

Quantity.	Description	Unit	Rates	
			In Figures	In Words
5	Rewinding of Submersible Pump Sets (BWSSB SR 14-15 P-58 I-A) 10 HP	No.	4785.00	Rupees Four Thousand Seven Hundred Eighty Five Only
40	(BWSSB SR 14-15 P-58 I-A) 7.5 HP	No.	3822	Rupees Three Thousand Eight Hundred Twenty Two Only
41	(BWSSB SR 14-15 P-58 I-A) 12.5 HP	No.	5885	Rupees Five Thousand Eight Hundred Eighty Five Only
42	(BWSSB SR 14-15 P-58 I-A) 15.0 HP	No.	5800	Rupees Five Thousand Eight Hundred Only
43	Pump Bowls (BWSSB SR 14-15 P-58 I-B)	No.	308.00	Rupees Three Hundred Eight Only
44	Intermediate Piece (I.P) With IP Leaded Bronxe bush (BWSSB SR 14-15 P-58 I-B2)	No.	715.00	Rupees Seven Hundred Fifteen Only
45	Upper Flange (BWSSB SR 14-15 P-59 I-C3)	No.	330.00	Rupees Three Hundred Thirty Only
46	Lower Housing (BWSSB SR 14-15 P-59 I-C4)	No.	539.00	Rupees Five Hundred Thirty Nine Only
47	Guide vane (BWSSB SR 14-15 P-58 I-B5)	No.	192.50	Rupees One Hundred Ninety Two and Fifty Paise Only
48	Impeller Shell moulded with aluminium Bronze) (BWSSB SR 14-15 P-58 I-B6)	No.	264.00	Rupees Two Hundred Sixty Four Only
49	Discharge outlet (D.O) Bearing D.O Steel Bush P. (BWSSB SR 14-15 P-58 I-B7)	No.	522.50	Rupees Five Hundred Twenty Two and Fifty Paise Only
50	Pump shaft made out of stainless steel Centreless ground with key way (upto 8 stages) (BWSSB SR 14-15 P-58 I-B10)	No.	660.00	Rupees Six Hundred Sixty Only
51	Pump Couping (Stainless Steel) (BWSSB SR 14-15 P-58 I-B12)	No.	341.00	Rupees Three Hundred Forty One Only
52	Stud and Nuts (BWSSB SR 14-15 P-59 I-C8)	Each	88.00	Rupees Eighty Eight Only
53	Motor Base With Pin (BWSSB SR 14-15 P-59 I-C11)	Each	407.00	Rupees Four Hundred Seven Only
54	Starter (with one year Guarantee) P No. 55 / I No. 10.3.3 PRED SR (2012-13)	No.	5050.00	Rupees Five Thousand Fifty Only
55	Rotor (with one year Guarantee) P No. 55 / I No. 10.3.6) PRED SR (2012-13)	No.	4700.00	Rupees Four Thousand Seven Hundred Only
56	Carbon Housing P. No. 56 / I No.10.3.12 PRED SR (2012-13)	No.	475.00	Rupees Four Hundred Seventy Five Only
57	Thrust bearing block assembly complete with Segment bearing pad.P. No. 55 / I No.10.3.13 PRED SR (2012-13)	No.	1150.00	Rupees One Thousand One Hundred Fifty Only
58	Oil Seal P. No. 54 / I No.10.2.3 PRED SR (2012-13)	No.	125.00	Rupees One Hundred Twenty Five Only
59	Oil Seal Steel Bush P. No. 54 / I No. 10.2.4 PRED SR (2012-13)	No.	150.00	Rupees One Hundred Fifty Only
60	D.O Bearing P. No. 44 / I No. 10.2.7 PRED SR (2012-13)	No.	285.00	Rupees Two Hundred Eighty Five Only
61	Steel Bush P. No.55 / I No. 10.2.9 PRED SR (2012-13)	No.	150.00	Rupees One Hundred Fifty Only
62	Allen Screw P. No.44 / I No. 10.2.9 RDPR SR (2012-13)	No.	25.00	Rupees Twenty Five Only
63	Pump Key (Stainless Steel) P. No. 45 / I No. 10.2.11 RDED SR (2012-13)	No.	125.00	Rupees One Hundred Twenty Five Only
64	Non - return valve (NRV) assembly complete with rubber 'O' Ring P. No. 55 / I No. 10.2.14 PRED SR (2012-13)	No.	1350.00	Rupees One Thousand Three Hundred Fifty Only
65	Cable Guard P. No. 55 / I No. 10.2.15 PRED SR (2012-13)	No.	150.00	Rupees One Hundred Fifty Only
66	Strainer P. No. 45 / I No. 10.2.15 RDED SR (2012-13)	No.	150.00	Rupees One Hundred Fifty Only
67	Brass Filter P. No. 55 / I No. 10.2.17 PRED SR (2012-13)	No.	250.00	Rupees Two Hundred Fifty Only

no of corrections - Nil

11/01
E.E. (B.T. DIV)
11/01

Quantity.	Description	Unit	Rates	
			In Figures	In Words
45	Labour Chargesw (Over Hauling Only) P. No. 45 / I No. 10.2.18 PRED SR (2012-13)	No.	556.00	Rupees Five Hundred Fifty Six Only
69	Re-erection charges of pumping machineries including overhauling and pointing P. No. 56 / I No. 10.3.20 PRED SR (2012-13)	Each	950.00	Rupees Nine Hundred Fifty Only
70	Lock Ring P. No. 45 / I No. 10.3.11 PREC SR (2012-13)	Each	85.00	Rupees Eighty Five Only
71	a) Carbon Housing P. No. 46 / I No. 10.3.12 APRDED SR (2012-13)	Each	475.00	Rupees Four Hundred Seventy Five Only
72	Top Carbon/Ferodo padding P. No. 46 / I No. 10.3.12 APRDED SR (2012-13)	Each	150.00	Rupees One Hundred Fifty Only
73	Bearing (Gunmetal) Centrifugal) Cast Aluminium Bronxe, Beaing bush P. No. 46 / I No. 10.3.16 APRDED SR (2012-13)	Each	400.00	Rupees Four Hundred Only
74	Circilpls P. No. 45 / I No. 10.3.17 PREC SR (2012-13)	Each	50.00	Rupees Fifty Only
75	15 Supplying & delivery at site brand new / Essen / Lotus sunsines/Adarsh/ Gk controls best indigenouse make combine energy meter-cum-control panel board unit of size 1200 x 600 x 300 mm minimum mechanically strong and vermin and water proof the unit shall have two detachable doors suitable for operation on 3ph, 50Hz, 380/440 volts, AC supply with spring loaded latch locking with a key ribs should be provided inside the door , canopy apron and louvers ventilators shall be provided the combine energy mtr cum control panel board unit suitable for operation on 3ph, 50Hz, 380/440 AC supply shall be consisted etc., completed T panel board shall be fabricated on single unit in the above components panel board for suitable pumpset above components panel board for suitable pumpset above 6.50 HP to 15.00 HP with star delta starter (MR)	No.	14800.00	Rupees Fourteen Thousand Eight Hundred Only
76	330000.00 Fabricating supplying and mounting MS box of 16 SWG suitable for floor / wall mounting, fully weather proof with provision for better hear description, (providing with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primes paint and finally finished with approved colour enamelled metal paint etc., complete box of 21600 sq cm (P.NO-530, I.NO-39 b, BWSSB SR 13-14)	Sqm	0.34	and Thirty Four Paise Only
77	1200.00 Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor conforming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto 1100 Volts. P. No. 49/ I No. 29-b(1) 4 Sqm mm of 56 strands 0.3mm dia Group - A KPWD Electrical SR 2010-11	Mtr	185.00	Rupees One Hundred Eighty Five Only
78	25.00 Supplying and fixing miniature circuit breakers/isolators in existing MCB distribution boards using necessary fixing materials and wiring complete as required, 40 to 63 Amps DP (P.NO - 526, I.NO - 13D (a), BWSSB SR 13-14)	No's	906.40	Rupees Nine Hundred Six and Forty Paise Only
79	45.00 Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc., complete.... P No. 32/I No 3b KPWD Electrical SR 2010-11	No.	150.00	Rupees One Hundred Fifty Only
80	60.00 Supplying & delivery of brand new best make non return valve of size 50mm as per IS: 778/84 with latest amendments with ISI mark (50mm Gate wheel Valve. (PWD SR 2015-16, P.NO.XXIV, SI.no, 673)	No's	1600.00	Rupees One Thousand Six Hundred Only
81	45.00 Providing and fixing of 50mm GI bend to motor (PWD SR 2015-16, P.NO.XXXVIII GI FITTINGS TABLE)	No's	219.00	Rupees Two Hundred Nineteen Only
82	45.00 Providing and fixing of 50mm GI Nipple to motor (PWD SR 2015-16, P.NO.XXXVIII GI FITTINGS TABLE)	No's	104.30	Rupees One Hundred Four and Thirty Paise Only
83	45.00 Providing and fixing of 50mm GI union to the motor (PWD SR 2015-16, P.NO.XXXVIII GI FITTINGS TABLE)	No's	223.70	Rupees Two Hundred Twenty Three and Seventy Paise Only

No of corrections - Nil

E.E. (BTP. DIV)
11/01

Quantity.	Description	Unit	Rates	
			In Figures	In Words
84 506.25	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications (P.NO - 5, I.NO - 2.4, PWD SR 15-16)	Cum	283.02	Rupees Two Hundred Eighty Three and Two Paise Only
85 1500.00	Providing and installing at site of work 75mm (0.662) PVC Pipes of 6 kg / cm ² including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe around to a depth not less than 15cms with gravel or selected earth available from the excavation etc., complete (P.NO - 102, I.NO - 13.73.1, PWD SR 15-16)	Mtr	366.76	Rupees Three Hundred Sixty Six and Seventy Six Paise Only
86 506.25	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications (P.NO - 6, I.NO - 2.11, PWD SR 15-16)	Cum	76.32	Rupees Seventy Six and Thirty Two Paise Only
87 10	KSRB 13.6.3-6 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 50mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No. KBS 13.2.6/13.3 P. 97 / I.13.37 PWD SR - 2015-16	Each	2120.00	Rupees Two Thousand One Hundred Twenty Only
88 1750.00	Threading of GI Pipes 50mm Dia P. No. 15 / I No.3.11.6 PRED SR (2012-13)	No.	25.00	Rupees Twenty Five Only
89 857.00	Supply of Drinking Water through water tankers of Capacity 6000 Liters and Hiring of Water Tanker Hiring of Tractor 40HP including cost of warer and Engaging Heavy Mazdoor to deliver water including cost of fuel lubricants men and machinary etc. complete including	Load	452.00	Rupees Four Hundred Fifty Two Only

No of corrections - Nil

Chandrasekhar
Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

- Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
- Unit rates and prices shall be quoted by the Tender in Indian rupees.
- Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a))
- Where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

DTS Approved

with 2nd & 1st correction

@ SI-No: 1 & 5

[Signature]
11-01-17